790 Industrial Way
Victoria, B.C. V9B 6E2
www.westerngrater.com

Date: Thursday May 9, 2019

NOTIFICATION OF: "DRILLING AND BLASTING"

Description of work to be done: Drilling and blasting for new 7 lot Subdivision, for road accses, services as per plan, Storm drain, sanitary lines, water and Hydro Tel trenches… Road accses will be completed by May 15… Blasting for services will be intermitted… as the contractor hits rock in the bottom of Service trenches

Drilling and Blasting will occur at: 2512 Duncan Plc.

Blasting will continue on Duncan Plc

Estimated duration of project: Approximately Two (2) month

Hours of Blasting: Monday through Thursday: 8:00 a.m. to 4:00 p.m.
Friday: 8:00 a.m. to 4:00 p.m.
(No blasting on Saturdays, Sundays or Statutory Holidays)

List of methods intended to be used to safeguard persons and property:

1. Blasting signs.
2. Blasting signals: _____As below_____
3. Warning signals will be as follows:
   - Twelve (12) short whistles, followed by a pause of up to 2 minutes;
   - Blast will be detonated;
   - A long whistle indicates all is clear.
4. Blasting mats are required.

City of Langford: 250-478-7882

Contact Name: Pete McBride
Western Grater Contracting Ltd.
250-478-4225

Independent Survey Company: Excel Adjustco 250-479-2842